



1. Kalzip Deck Roof.
2. 150mm Kalzip Rockwool insulation to achieve U.Value of 0.25.
3. Kalzip Breather Membrane.
4. Structural Deck.
5. Purlins by others.
6. Rafters to be sized by SE.
7. Line of parapet.
8. Kalzip pre-formed insulated rigid gutter.
9. Aluminum flashing cover.
10. Fully Louvered Elevation. Louvres tied back to the existing structure.
11. All Steelwork to be sized by SE.
12. Gutter dressed to underside of curtain walling parapet.
13. Glass mimic panel in curtain walling mullions. Glass to wrap around forming parapet.
14. Kalzip roof dressed under mullion and sealed.
15. Aluminium soffit

